



AQABA NEW PORT INFORMATION

AQABA NEW PORT BERTHS PARTICULARS

Drafts for berth (1) and (2): 14m

Drafts for berths (3) and (4): 12m

AQABA NEW PORT HANDLING CAPABILITIES

A - 2 Mobile Cranes / Handling Rate = 100 tons per 1mobile

B - 7 Cranes / Handling Rate = (30 - 120 Tons)

C - 67 Forklifts / HR = (3 - 28 Tons)

D - 23 Trailers / HR = (40 - 120 Tons)

E - 28 Mafi Tractors / HR = (40 - 120 Tons)

** Mobile Cranes will remain at the Old Port until June; then, it will be relocated to the new port during June 2018 as expected, Therefore, any Vessels require Mobile cranes; it will be handled at the Old Port until the mobile crane is being relocated to The New Port.

AQABA NEW PORT ROADS PARTICULARS

Description	Allowable Axle Load (KN)	Allowable Baring Load (Kg/M2)
Asphalt Yards & Roads	98	28561
Concrete Blocks/ Interlock Tiles with Cement Treated Base Course	995	32761
Concrete Rigid Pavement	226	21025